

# The DESIR facility at GANIL/SPIRAL2

**Bertram Blank**

**L2Pi Bordeaux**




**Séminaire IJCLab, 13/12/2024**




### A new GANIL users facility

- Study of the fundamental properties of atomic nuclei and underlying forces
- With a high precision using ultra-pure samples of radioactive ions manipulated at very low energy
- Taking advantage of the various RIBs production methods
- In complementarity to  $S^3(-LEB)$  and other GANIL installations

● ● ● **DESIR at GANIL**



Building delivery:	mid-2025
Commissioning (stable beams):	2027
Day 1 experiments (RIBs):	2028



# DESIR physics programme

- Collinear laser-spectroscopy
- Correlations in  $\beta$  decay (MORA)
- Mass meas. (PIPERADE, MLLTrap)
- (Trap-assisted) decay spectroscopy

LUMIERE

DETRAP

BESTIOL

SPIRAL 1

## Fragmentation

ECR source

FEBIAD

Surface ionization

TALEAU PÉRIODIQUE DES ÉLÉMENTS



ECR: Ne, Ar, Kr, N, O, F  
 Surface ionization: Li, Na, K, Rb  
 FEBIAD: Mg, Al, P, S, Cl, Fe, Cu

Courtesy of P. Delahaye

✓ Exotic decay modes



✓ Nuclear structure

✓ Fundamental interactions



# Beam production

● ● ● SPIRAL1 beams




## Fragmentation (and fus-eva) of heavy primary beams

### Limitations:


- primary beam power
- fragmentation cross sections
- diffusion/effusions times (refractory elements, short half-lives)
- ionisation efficiency
- operational issues (stability, resilience etc.)

● ● ● S3-LEB beams



- ❑ Critical performance criteria :
  - Stopping efficiency
  - Extraction efficiency and time
  - Chemical survival/neutralization efficiency

**S<sup>3</sup>-LEB**  
(Low Energy Branch)







# S3-LEB beams: FRIENDS<sup>3</sup>



- ❑ ANR JCJC project FRIENDS<sup>3</sup> aimed at improving the S<sup>3</sup>-LEB gas cell:
  - Reduce extraction time
  - Improve neutralization efficiency
  - Ideally both at the same time

## Construction of test bench


## Simulations



- ❑ Test-bench design study finalized, constructed in 2024
- ❑ Will be installed at GANIL for laser access
- ❑ Exploration of direct ion extraction by electrical field



● ● ● **DESIR beams: S1 & S3 (& S2)**





**DESIR beams:**  
**S1: fragmentation**  
**S3: fusion-  
evaporation**  
**S2: fission**  
**Multi-nucleon  
transfer reactions**

# Beam transport

# ● ● ● Transport beam lines

1+ ions, < 60 keV, < 80  $\pi$ .mm.mrad – fully electrostatic



Test bench

LP2i  
Bordeaux

Ph. Alfaut, LP2iB

DESIR  
Hall

SP1 -> DESIR beam line



V. Watt-Morel, GANIL




L. Perrot et al., IJCLab

SP1RAL1

- Junction beam lines from SPIRAL1 and S3-LEB to the DESIR Hall: ~100 m
- Installation starting by the end of 2025





## Example: 45° deflector assembly



# ● ● ● Transport beam lines

## SPIRAL -> DESIR section


- Ongoing installation (mechanical assembly, supply integration tests, ...)
- Operation tests scheduled middle of 2025
- LP2IB/GANIL: process supplies, remote control systems...





# Beam preparation and purification

# ● ● ● Beam preparation and purification



## Mass separation/beam purification:

RFQ+HRS

- $\frac{M_0}{\Delta M} = \sim 20\,000$

MR-ToF

- $\frac{M_0}{\Delta M} = \sim 200\,000$

Piperade  
1<sup>st</sup> trap

- $\frac{M_0}{\Delta M} \leq 10^5$

Piperade  
2<sup>nd</sup> trap

- $\frac{M_0}{\Delta M} \approx 10^6 - 10^7$

## Beam preparation:

GPIB

- Cooling and bunching

Piperade  
2<sup>nd</sup> trap

- Accumulation trap

## Mass measurements:

Piperade  
2<sup>nd</sup> trap

- Mass precision:  $10^{-8} - 10^{-9}$

● ● ● Beam purification




**RFQ + HRS**

**M/ΔM = 20,000 @  
3π mm.mrad / 30keV**




**GPIB + PIPERADE**

**10<sup>5</sup> ions/bunch, 2-20 Hz M/ΔM = 10<sup>5</sup>**



**Refurbishment  
at LPC Caen**

**Commissioning at LP2iB**



**Commissioning at LP2iB**

- Installation and commissioning: 2026-2027
- MR-ToF-MS for mass measurements and beam purification: 2026-2028

● ● ● **Beam purification: RFQ SHIRaC**




**SHIRaC : Construction and test @ LPC Caen**



**HT platform 60 kV**  
**RF Electrical Field: 500V/m**

R. Boussaid et al., PRCST 18 (2015) 072802



**SHIRaC**  
RF: 2.1-4.9 MHz;  $V_{pp}$ : 8kV  
Emittance:  $\sim 3\pi$  mm.mrad  
 $\Delta E \sim eV$   
Transmission  $\sim 70\%$  for 1 $\mu A$  beam

...presently refurbished at LPC  
(according to RFQ cooler of SPES)



● ● ● Beam purification: Ion source, GPIB, PIPERADE and HRS at LP2i Bordeaux


High Resolution Separator  
**HRS**

source  
d'ions


RFQ-Cooler Buncher  
**GPIB**

Double piège de Penning  
**PIPERADE**  
PIEGES DE PENNING POUR LES REACTEURS A DESER



Ion  
source



# ● ● ● Beam purification: High-resolution separator HRS




Configuration: MQ-MQ-FS-FQ-D-M-D-FQ-FS-MQ-MQ




$M/\Delta M = 20\ 000 @ 3\pi \text{ mm.mrad} / 30\text{keV}$



# Beam purification: High-resolution separator HRS




# High-resolution separator 2<sup>nd</sup> order correction measurements





> Shifted left -0,2G  
 > Shifted right +0,2G

Beam can be scanned with the dipoles through end slits to obtain a precise beam profile




48-rod multipole


POWER ON	POWER OFF	QUADRUPOLE	SEXTUPOLE	OCTUPOLE	DECAPOLE		
Ramp: 20 %/s							
Amplitude (V)		0	100	0	0		
PHASE (°)		0	0	0	0		
Vact max   100 V							
Power	EQPT	VCons	VAct	VAct	VCons	EQPT	Pow
✓	LHR-M31-P0	-19.51 V	-19.4 V	19.5 V	19.51 V	LHR-M31-P27	✓
✓	LHR-M31-P1	-55.56 V	-55.5 V	55.6 V	55.56 V	LHR-M31-P46	✓
✓	LHR-M31-P2	-83.15 V	-83.1 V	83.2 V	83.15 V	LHR-M31-P45	✓
✓	LHR-M31-P3	-98.08 V	-98.1 V	98.1 V	98.08 V	LHR-M31-P44	✓
✓	LHR-M31-P4	-98.08 V	-98.1 V	98.1 V	98.08 V	LHR-M31-P43	✓
✓	LHR-M31-P5	-83.15 V	-83.2 V	83.1 V	83.15 V	LHR-M31-P42	✓
✓	LHR-M31-P6	-55.56 V	-55.5 V	55.5 V	55.56 V	LHR-M31-P41	✓
✓	LHR-M31-P7	-19.51 V	-19.5 V	19.5 V	19.51 V	LHR-M31-P40	✓
✓	LHR-M31-P8	19.51 V	19.5 V	19.5 V	19.51 V	LHR-M31-P39	✓
✓	LHR-M31-P9	55.56 V	55.6 V	55.6 V	55.56 V	LHR-M31-P38	✓
✓	LHR-M31-P10	83.15 V	83.1 V	83.1 V	83.15 V	LHR-M31-P37	✓
✓	LHR-M31-P11	98.08 V	98.1 V	98.1 V	98.08 V	LHR-M31-P36	✓
✓	LHR-M31-P12	98.08 V	98.1 V	98.1 V	98.08 V	LHR-M31-P35	✓
✓	LHR-M31-P13	83.15 V	83.2 V	83.2 V	83.15 V	LHR-M31-P34	✓
✓	LHR-M31-P14	55.56 V	55.5 V	55.5 V	55.56 V	LHR-M31-P33	✓
✓	LHR-M31-P15	19.51 V	19.3 V	19.5 V	19.51 V	LHR-M31-P32	✓
✓	LHR-M31-P16	-19.51 V	-19.6 V	-19.5 V	-19.51 V	LHR-M31-P31	✓
✓	LHR-M31-P17	-55.56 V	-55.6 V	55.6 V	55.56 V	LHR-M31-P30	✓
✓	LHR-M31-P18	-83.15 V	-83 V	83.2 V	83.15 V	LHR-M31-P29	✓
✓	LHR-M31-P19	-98.08 V	-98 V	98.1 V	98.08 V	LHR-M31-P28	✓
✓	LHR-M31-P20	-98.08 V	-98.1 V	98.1 V	98.08 V	LHR-M31-P27	✓
✓	LHR-M31-P21	-83.15 V	-83.2 V	83 V	83.15 V	LHR-M31-P26	✓
✓	LHR-M31-P22	-55.56 V	-55.6 V	55.5 V	55.56 V	LHR-M31-P25	✓
✓	LHR-M31-P23	-19.51 V	-19.6 V	19.4 V	19.51 V	LHR-M31-P24	✓



Front view:  
tantal mask






Side view:  
Phosphore screen + MCP



Front view:  
CCD camera



Pepperpot  
emittance-meter






Experimental measurements correspond to simulations


2<sup>nd</sup> order aberrations can be observed with the emittance-meter  
→ Order 3: Not by eye, but a computer could  
→ Image analysis software under development  
(A. Balana)






> Shifted left -0,2G  
> Shifted right +0,2G




Beam (1mm x 1mm) can be scanned with the dipoles through exit slits to obtain a precise beam profile



Pepperpot emittance figures





Beam (1mm x 1mm) can be scanned with the dipoles through exit slits to obtain a precise beam profile




Hard to see a change, but a computer should





# High-resolution separator HRS: arbitrary waveform generator



$$Energy_{total} = 25000eV + custom\ distribution (\pm 5eV)$$




Create custom beam contaminants




The HRS can be commissioned in almost real operating conditions, with no radioactive beam and (relatively) high intensities


# High-resolution separator HRS: arbitrary waveform generator




$$Energy_{total} = 25000eV + custom\ distribution (\pm 5eV)$$



**$^{100}\text{Sn}/^{100}\text{In}$  separation:  
simulation and measurement**




# High-resolution separator HRS: arbitrary waveform generator







## To-do list:

- shaping of exit (1<sup>st</sup> dipole) and entrance (2<sup>nd</sup> dipole) poles  
 → fixed hexapole corrections
- optimising of 3<sup>rd</sup> and higher orders
- implementation of automatic higher-order corrections
- NMR measurement reliability improvement



$^{100}\text{Sn}/^{100}\text{In}$  separation:  
simulation and measurement






## To-do list:



- Magnetof for energy dispersion (avoid efficiency issues)
- Transverse emittance measurements in bunching mode
- RF phase dependence for the bunches
- Bunching mode to be investigated in detail (energy vs time dispersion)
- Space charge effects
- coupling to HRS ?

## Energy and time dispersion:


- Energy dispersion measurement currently limited by detection system ( $< 6$  eV)  $\rightarrow$  Magnetof
- Minimum time dispersion currently down to  $\approx 250$  ns (FWHM) at 3 keV



● ● ● Beam purification: PIPERADE, 1<sup>st</sup> trap






First trap:



Resolving power:

$$\frac{\nu_c}{\Delta\nu_c} \propto \frac{m}{\Delta m} \approx 2 \times 10^5$$


● ● ● Beam purification: PIPERADE, 2<sup>nd</sup> trap



accuracy:  $\frac{\Delta m}{m} \approx 9.5 \times 10^{-10}$

precision:  $\frac{\delta m}{m} \approx 3 \times 10^{-9}$



$$\nu_c = \frac{\phi_c + 2\pi n}{2\pi t} = \frac{qB}{2\pi m}$$



accuracy:  $\frac{\Delta m}{m} * 5$

precision:  $\frac{\delta m}{m} * 40$

# PIPERADE: Mass measurement of $^{41}\text{K}$ with ToF-ICR



- measured with  $^{39}\text{K}$  as reference
- ToF-ICR of 1 s




$$v_c = \frac{qB}{2\pi m}$$

$$v_c = \frac{\phi_c + 2\pi n}{2\pi t} = \frac{qB}{2\pi m}$$

$$\delta v_c = \frac{\delta \phi_c}{2\pi t} = \frac{\delta r}{2\pi r t \sqrt{N}}$$

Précision  $\frac{\delta m}{m} \approx 10^{-8}$  à  $10^{-10}$

position-sensitive MCP





## **To-do list:**


- **January 2025: diaphragm change for a smaller diameter hole (reduction of gas leaking from PT to MT)**
- **before moving to DESIR:**
  - **systematic studies of ToF-ICR, impact of field imperfections (anharmonicities of E-field and fluctuations of B-field) on mass precision, mass-dependent errors, ion-ion interaction**
  - **PI-ICR mass measurement and systematic studies (imperfections E/B fields + image distortion + extraction optimisation)**
  - **PI-ICR cleaning: installation of an iris to select the ion of interest**
  - **Buffer gas cooling technique: limits in terms of trapping times and investigation vs number of ions**
- **if AC not OK at DESIR: pressure/temp stabilisation system to implement**
- **commissioning at DESIR: all systematics to study again**



# Installation of experimental equipment


● ● ● Experimental equipment: time line

S2 - 2026: GPIB + PIPERADE + fluorescence laser line (LINO)



● ● ● Experimental equipment: time line


S1 - 2027: MORA cooler-buncher (RFQ)



● ● ● Experimental equipment: time line


2028: **MORA** completed, **MR-ToF-MS**, decay stations

*028: RIBs available*



# Experimental equipment: time line

2029: collinear laser spectroscopy (**LASAGN**) completed, **MLLTrap**




# • • • The DE<sub>sir</sub>TRAP<sub>ping</sub> facility

## MORA

*P. Delahaye, GANIL, L. Hayen, X. Fléchar, LPC Caen*

- RFQ-CB associated with a Paul trap
- >  $\beta$ - $\nu$  angular correlation coefficient
- > D correlation with laser polarized beams



*P. Delahaye et al., Hyperfine Interaction 240 (2019) 63*

⇒ Fundamental interaction physics


- exotic currents, CVC,  $V_{ud}$ , CP-violation

Commissioning at JYFL

## MLLTrap

*P. Thirolf, LMU Munich – E. Minaya Ramirez, IJCLab*

- Double Penning trap
- > high precision mass measurements
- > in-trap decay



*E. Minaya-Ramires et al., NIM B 463 (2020) 315*

*P. Chauveau et al., NIMB 463 (2020) 371*

⇒ Nuclear structure & Decay properties

- shell evolution, deformation
- (super-) heavy nuclei decay spectroscopy


Commissioning at ALTO (IJCLab)

# • • • The LUMIERE facility

## Laser Utilization for Measurement and Ionization of Exotic Radioactive Elements

### LASAGN (L. Lalanne, IPHC)

- Collinear laser spectroscopy (CRIS like)
  - > hyperfine structure (magnetic and quadrupole moments, mean square charge radii)
- LINO commissioned at ALTO, IJCLab, D. Yordanov et al.





# ● ● ● The BESTIOL facility

BETA decay STUDIES at the SPIRAL2 IsOL facility


Beam cooling and purification using PIPERADE for (trap-assisted) decay spectroscopy

-> High-precision measurements with ultra-pure samples for fundamental interaction, nuclear structure, nuclear astrophysics etc


- $\beta$ - $\gamma$  decay stations (BEDO, ...)
- total absorption spectrometers (DTAS)
- neutron detection arrays (BELEN, MONSTER, ...)
- electron and proton detection (COeCO, SiCube, b-STILED)
- recoil detection (ASGARD)

for


- CVC,  $V_{ud}$
- beta shapes
- lifetimes,  $P_{(2)n}$
- exotic decays ( $\beta$ -2p, cluster emission)
- Gamow-Teller strength



BELEN




ASGARD



COeCO




SiCube



BEDO



b-STILED




MONSTER





DTAS





## ● ● ● The DESIR building



- **Building delivery: September 2025**
- **October 2025 to September 2026: Beam line & experiment installation**
- **June 2026 to January 2027: Cabling**
- **October 2026 to June 2027: Technical commissioning**
- **March to October 2027: Stable beam commissioning**
- **November 2027: Facility ready for radioactive beams**

● ● ● **DESIR construction**



**HRS room**



**DESIR hall**




**Thermal isolation of roof**



**Soil refilling**

# DESIR time line



Thanks for your attention

