

The Henryk Niewodniczański
Institute of Nuclear Physics
Polish Academy of Sciences

The experience gained by IFJ PAN
and its implementation into the projects





Dariusz Bocian
Jacek Świerblewski




The Division of Scientific Equipment and Infrastructure Construction (DAI)



- Personnel: **561**; Prof. **30**, Assoc. Prof. **61**, Ph.D. **101**, engineers **117**
- Scientific Divisions:
 - Division of Particle and Astroparticle Physics
 - Division of Nuclear Physics and Strong Interactions
 - Division of Condensed Matter Physics
 - Division of Theoretical Physics
 - Division of Interdisciplinary Research
 - Division of Applications of Physics
- Researcher Departments:
 - Cyclotron Centre Bronowice
 - Division of Scientific Equipment and Infrastructure Construction
 - Four accredited laboratories
- Education:
 - International Ph.D. Studies
 - Interdisciplinary Doctoral Studies
 - Kraków Interdisciplinary Doctoral School
- Scientific output: **> 650** publications annually









- **1955** – foundation of the IFJ – as a branch of the Institute of Nuclear Research – Prof. Henryk Niewodniczański (1900-1968)



(Fot. Archiwum of the IFJ PAN)

- **1960** – IFJ as a standalone unit
- **1970** – Particle physics enters – Prof. Marian Mięśowicz (1907-1992)
- **1988** – IFJ gets the name of its patron – Henryk Niewodniczański
- **2003** – IFJ gets the status of a Research Institute of Polish Academy of Sciences







Participation of IFJ PAN in projects aimed at the Development of Innovation and Cooperation of European Technological Infrastructures for Accelerators and Magnets



TIARA – Test Infrastructure and Accelerator Research Area (2 years, 2011-2013)

In Poland, the project was carried out by a consortium of 7 scientific institutions: the Henryk Niewodniczański Institute of Nuclear Physics of the Polish Academy of Sciences, the AGH University of Science and Technology, the Cracow University of Technology, the Andrzej Sołtan Institute of Nuclear Problems, the Warsaw University of Technology, the Lodz University of Technology, the Wrocław University of Technology.



AMICI – Accelerator and Magnet Infrastructure for Cooperation and Innovation (2017-2019)

In Poland, the project was carried out by the Henryk Niewodniczański Institute of Nuclear Physics of the Polish Academy of Sciences



i.FAST – Innovation Fostering in Accelerator Science and Technology (2021-2025)

WP13 activities are carried out by the Henryk Niewodniczański Institute of Nuclear Physics of the Polish Academy of Sciences




FuSuMaTech - Future Superconducting Magnet Technology (2017-2019, 2021-2025)

In Poland, the project is was carried out by the Henryk Niewodniczański Institute of Nuclear Physics of the Polish Academy of Sciences



GSI, FAIR, and Super-FRS

courtesy GSI/FAIR Colleagues



Primary Beams

- $3.5 \cdot 10^{11}$ $^{238}\text{U}^{28+}/\text{s}$ (DC) @ 1.5 GeV/u
- $5 \cdot 10^{11}$ $^{238}\text{U}^{28+}$ (pulsed) @ 1 GeV/u
- factor **100-1000** in intensity over present

Secondary Beams





- Broad range of short-lived (= "exotic") beams up to **1.5 GeV/u**
- up to **factor 10 000** in intensity over present (GSI+FRS)



NUclear Structure, Astrophysics, and Reactions



FAIR: string test interconnection areas



courtesy GSI/FAIR Colleagues

SCHEDULE AIK 10.1-Cryomodule test


- Reception of Cryomodule units
- Preparation of Cryomodule units for the test bench
- Installation on the test bench
- Initial testing
- Cool down
- Heat load measurements
- Warm up
- Disconnection
- Preparation for the tunnel
- Participation in site activity coordination
- Final review



2017 - 2026


SCHEDULE AIK 8.6 -RF Installation

- Stub installation
- LLRF installation
- LPS installation
- Distribution system installation
- High Power Amplifier installation



SCHEDULE AIK 17.3 -PC Installation

- Klystrons Modulators for RFQ and DTL
- Klystron Modulators for Medium / High Beta
- Magnet Power Converters



SCHEDULE AIK 8.8

CONTRIBUTION TO THE LOW AND HIGH-POWER TESTS OF RF EQUIPMENT AND TESTING AND INSTALLATION OF RFPS'S IN TS3 AND IN G02.

2022 - 2023



THE HENRYK NIEWODNICZAŃSKI
INSTITUTE OF NUCLEAR PHYSICS
POLISH ACADEMY OF SCIENCES



EUROPEAN
SPALLATION
SOURCE


- Cryogenic experts,
- Mechanical and electrical specialists,
- RF engineers,
- Vacuum specialists,
- Skilled technicians,



MECH inspection



VAC activities



CRYO operations



ELE measurements






TECH work



Supported activities at ESS side

- ▶ Support with installation trial of elliptical CM05 & spoke CM02 in the tunnel,
- ▶ Support with SPOKE CM10 CTS motor replacing,
- ▶ Replacing of the LG at all SPOKE CM's,
- ▶ Various leak tests for choosen SPOKE CM's,
- ▶ Support with MLI installation for ACCP-CTL interconnections,
- ▶ And ...





Documents

- 10 procedures
- 47 reports
- 15 check lists
- 13 NCR's

all documents in CHES system

3DEXPERIENCE | Document Management

Asset Documentation ESS Project Accelerator Accelerator Collaborative

Name	Status	Version	Release
Asset Documentation			
Medium Beta Cavities			
Medium Beta CM Assembly			
Medium Beta CM Parts			
Medium Beta CM Operation			
CM01			
CM03			
CM04			
CM00			
CM05			
ESS-3730754			
ESS-3739897			
ESS-3837787	1	✓	
ESS-3843954	1	✓	
ESS-3833407	1	✓	
ESS-3918520	1	✓	

NCR

Non-Conformity Report
ESS-4169327

3. NON-CONFORMITY DESCRIPTION

DETAILED DESCRIPTION OF THE NON-CONFORMITY
During preparing for rough leak test of the cryogenic lines background the beginning at almost 2.0e-5 mbar%/s. Cryogenic lines has not connections. Thermal shield circuit, 4K line and 2K volume has to determine at which volume leak is expected. During pumping down line no change for leak rate of helium was observed. Significant was observed during pumping down of the 2K volume (fig. 1).

Fig. 1

It was decided to do verify quality of the During visual inspection interconnection. At 4K (Fig. 2).

cryogenic check list

AFTER WARM-UP CHECK LIST

Cryomodule number

Step	Check	Sub-check
1	Level meter - OFF	Temp >50K
2	EPICS - CHECK	All temperature sensors ABOVE 288K, especially TE-018, TE-82306, TE-82385
3	Heaters in MANUAL MODE,	EH-013

electrical procedure

12. PT-100 ON COUPLERS COOLING OUTLET (EXTERNAL)

Measuring equipment: Keithley 2701
Repeat the following for all the 4 PT-100 sensors (TT-015, TT-025, TT-035, TT-045):

IMPORTANT!!!
For PT-100 sensors the excitation current must be set to 100uA

12.1. All-pins combinations test (2-wire mode)

12.1.1. Measuring device preparation:

- Disconnect all the cables from the front panel of the Keithley 2701,
- Reset the meter to its factory defaults,
- Set measuring mode to Ohms 2-wire,
- Make sure that the integration time (measurement speed) is set to "SLOW",
- Set range to 10kOhm.

12.1.2. Connections:

- Prepare LEMO4-banana cable.

12.1.3. The measurement:

- Perform measurement according to the report's template pinout and write down the resistance for each combination.

12.2. 4-wire resistance test

12.2.1. Measuring device preparation:

- Disconnect all the cables from the front panel of the Keithley 2701,
- Starting configuration is as after the previous test,
- Set measuring mode to Ohms 4-wire,
- Make sure that the integration time (measurement speed) is set to "SLOW",
- Set range to 10kOhm.

vacuum report

Date: Aug 29, 2022
State: Released
Confidentiality Level: Internal

vacuum report

3.1.3. TEST RESULTS

mechanical report

Date: Feb 15, 2022
State: Released
Confidentiality Level: Internal

2.18. Coupler helium outlet (4 elements)

Check if the coupler helium outlet is undamaged (mechanically).

1	2	3	4
OK	NOK	OK	NOK
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Comments:

Check if all screws, washers and nuts are installed and not loose.

1	2	3	4
OK	NOK	OK	NOK
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Comments:

Check if the mechanical protections of the coupler heaters are installed.

1	2	3	4
OK	NOK	OK	NOK
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Comments:

Check if the connectors and pins of the heating cartridges [1] and the PT100s [2] are

1	2	3	4
OK	NOK	OK	NOK
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Comments:

PIC check list

Date: Sep 21, 2022
State: Released
Confidentiality Level: Internal

PIC check list

16	Blank flange for SV90	3387220	1 pcs		
17	Blank flange	3331600	10 pcs		
18	Male VCR1/4" cap	3331430	10 pcs		
19	Male	3331430	10 pcs		

vacuum procedure

Date: Jun 23, 2022
State: Released
Confidentiality Level: Internal

chamber / access hatch

PT100	1	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	2	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	3	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	4	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	5	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	6	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	7	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>
PT100	8	OK	NOK
		<input type="checkbox"/>	<input type="checkbox"/>

Comments:

rubber gaskets



High Power test procedure includes:

- DC conditioning;
- RF conditioning;
- RF test to check the functionality of the klystron.




Low Power test includes:

- Checking the cables;
- Checking electronic devices installed in RACK's;
- Setting the interlocks thresholds;
- Checking the response in GUI.



Additional tasks done by IFJ PAN:

- Klystron preparation before LPT;
- Filling klystron with oil;
- Participation during cavity tuning in NCL klystron (together with Thales and ESS experts);
- Participation during swapping the vacuum tube for CPI klystron between two magnet





LHC - construction, commissioning, consolidation

Signing of the agreement in 2005-2010 between IFJ PAN

- ✓ Design and implementation of automatic measurement systems for testing superconducting LHC circuits
- ✓ Quality Control of superconducting electrical circuits
- ✓ Inspection of LHC superconducting magnet connections



Quality Control of superconducting electrical circuits
ELQA TEAM

LHC during Long Shutdown




New measurement systems



*Damage disclosed during QC-
ICIT TEAM*

- ✓ The work managing of the multinational team "Alpha-Omega"






Standard ELQA measurements in the LHC during Long Shutdown 2.



- Standard measurements on more than 1600 LHC superconducting circuits and their instrumentation before and after warm-up of the LHC.
- Software development, design and fabrication of four dedicated diode lead measurement systems.

Up to 25 engineers and technicians from IFJ PAN on CERN site



Number of ELQA measurements performed by IFJ PAN personnel during LS2 until the end of 2020.



CERN CH-1211 Geneva 23
Document ID: 2044870 | REV: 2.0 | STATUS: RELEASED
Project: LHC-DQB-TP-0005
Title: LHC
Date: 2019-11-12

TEST PROCEDURE

Dipole Diode Lead Measurement in the LHC

ABSTRACT
This procedure describes a measurement method to determine the electrical resistance of the diode diode leads in the LHC machine. The scenario in which the diode capacitor is opened is included.

DOCUMENT PREPARED BY: H. Bednarek, G. D'Angelo, J. Lublin, D. Wajda	DOCUMENT CHECKED BY: C. Adriaens, M. J. Becharof, M. Benardis, N. Bourgeois, G. D'Angelo, R. Denis, A. Devedis, C. Ducas, G. Favia, P. Fréchet, M. G. H. Hagedorn, G. Hagedorn, T. Otsu, J. Paris, Espinosa, A. L. Reinos, G. S. Pina, M. Ripper, L. Ripper, S. Ruyter, C. Schwaninger, D. Schwaninger, S. Tournier, L. Van Der Bruggen, R. Yachou, B. Yousif, A. P. Zia, C. Zanfir, T. Zickler	DOCUMENT APPROVED BY: J. M. Simeoni, J.-R. Tuck
---	---	---

DO NOT COPY OR REPRODUCE THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF CERN

CERN CH-1211 Geneva 23
Document ID: LHC-DE-TP-0007 rev. 2.0 | REV: 2.0 | STATUS: RELEASED
Project: The Large Hadron Collider project
Title: ELQA
Date: 2013-02-01

Test procedure

ELQA QUALIFICATION OF THE SUPERCONDUCTING CIRCUITS DURING HARDWARE COMMISSIONING

Abstract
The purpose of this specification is to define the sequence of the qualification tests, the technical requirements, the organizational aspects and the safety rules for the successful electrical qualification (ELQA) of the superconducting circuits during the hardware commissioning of a LHC sector. The procedures, the ELQA 774 and the ELQA 802 are presented. This includes the qualification of the circuits presented on the DQAs and the qualification of the diode with corrections, respectively. In the present version of the document a new ELQA 802 procedure is added, the chapter related to the different scenarios was also revised and the test parameters for the high voltage qualification tests were modified in case of the separation of LHC at central energy after the long shutdown 1 (LS1).

Prepared by: Mateusz Bednarek Dawid Bielecki Vladimir Chuvpilo Sergey Lashin Nuria Catalán Loberans Giuseppe D'Angelo Richard Momo	Checked by: Amalia Bellarino Irene Casca Caballero Sergey Chuvpilo Sergey Lashin John Robert Elloridge Sébastien Falgar Michele Andros Suzanne Chuvpilo Andreas Bortone Gija De Nijk Nikolay Tsibulsky Indrek Brenner Knut Oskamp Katy Foray Jean-Philippe Tuck Miko Pfeifer Krzysztof Wroblewski Borisland Anuchin Andreas Momo	Approved by: Andrzej Sienkowiak Rudiger Schmidt Frederik Boudry Lucia Sartore Sergey Lashin Paul Collier Hilke Lorenz Laurent Favard Jean-François Barrot Thomas Otto
---	---	---

DO NOT COPY OR REPRODUCE THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF CERN

CERN CH-1211 Geneva 23
Document ID: 1485420 | REV: 1.0 | STATUS: RELEASED
Project: LHC
Title: LHC-MB-TP-0016
Date: 2022-10-26

TEST PROCEDURE

Investigation of the RB.A56 Fault to Ground

ABSTRACT
During the preceding tests after LS1 a fault to ground on the RB.A56 occurred on 3 Feb 2023. Other earth faults have occurred in the past, most recently during the CSOT tests in Oct 2014.

This document describes the measurement equipment that will be installed in order to improve the precision of the fault location in case a similar fault will reappear. Furthermore, a sequence of tests is described that will be followed in order to increase the current again to nominal. Of course the response will be interrupted in case a new fault to ground appears.

PREPARED BY: M. Bednarek, TEWPE J. Lublin, TEWPE	TO BE CHECKED BY: A. Varnas (on behalf of IEP) L. Sartore J.-R. Tuck J.-M. Couet C. Ducas T. Otsu J. Pedersen A. Reinos J. Trenner	TO BE APPROVED BY: P. Boudry S. Collier (on behalf of LHC) J.-M. Couet C. Ducas J. Otsu J. Pedersen A. Reinos J. Trenner
--	--	---

DO NOT COPY OR REPRODUCE THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF CERN

CERN CH-1211 Geneva 23
Document ID: 2044866 | REV: 1.0 | STATUS: RELEASED
Project: LHC-DE-TP-0025
Title: LHC
Date: 2019-09-03

Test Procedure

LS2 Partial Assembly Qualification (LS2-PAQ) Test Procedure

ABSTRACT
This document describes the electrical test procedure at room temperature that shall be applied on the LS2 diode array during the Diode Isolation and Superconducting Magnet Commissioning (DSIMC) project during the LS2.

DOCUMENT PREPARED BY: H. Bednarek, G. D'Angelo, J. Lublin, D. Wajda	DOCUMENT CHECKED BY: C. Adriaens, M. J. Becharof, M. Benardis, N. Bourgeois, G. D'Angelo, R. Denis, A. Devedis, C. Ducas, G. Favia, P. Fréchet, M. G. H. Hagedorn, G. Hagedorn, T. Otsu, J. Paris, Espinosa, A. L. Reinos, G. S. Pina, M. Ripper, L. Ripper, S. Ruyter, C. Schwaninger, D. Schwaninger, S. Tournier, L. Van Der Bruggen, R. Yachou, B. Yousif, A. P. Zia, C. Zanfir, T. Zickler	DOCUMENT APPROVED BY: J. M. Simeoni
---	---	--

DO NOT COPY OR REPRODUCE THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF CERN

CERN CH-1211 Geneva 23
Document ID: 2044866 | REV: 1.0 | STATUS: RELEASED
Project: LHC-DE-TP-0025
Title: LHC
Date: 2019-09-03

PROCEDURE

PROCEDURE OF ASSEMBLY FOR THE WARM MAGNETIC SHIELD (CRAB CAVITY PROJECT, DQW VERSION, SPS TEST)

Abstract
This procedure describes the assembly process of the warm magnetic shield inside the vacuum vessel.

ABSTRACT
This document describes the electrical test procedure at room temperature that shall be applied on the LS2 diode array during the Diode Isolation and Superconducting Magnet Commissioning (DSIMC) project during the LS2.

DOCUMENT PREPARED BY: H. Bednarek, G. D'Angelo, J. Lublin, D. Wajda	DOCUMENT CHECKED BY: C. Adriaens, M. J. Becharof, M. Benardis, N. Bourgeois, G. D'Angelo, R. Denis, A. Devedis, C. Ducas, G. Favia, P. Fréchet, M. G. H. Hagedorn, G. Hagedorn, T. Otsu, J. Paris, Espinosa, A. L. Reinos, G. S. Pina, M. Ripper, L. Ripper, S. Ruyter, C. Schwaninger, D. Schwaninger, S. Tournier, L. Van Der Bruggen, R. Yachou, B. Yousif, A. P. Zia, C. Zanfir, T. Zickler	DOCUMENT APPROVED BY: J. M. Simeoni, J.-R. Tuck
---	---	---

TRACEABILITY

Prepared by:	A. Kravacka (EN MMS/EP)	Date:	2017-07-01
Verified by:	M. Garbino (EN MMS/EP)	Date:	2017-08-01
Approved by:	G. Casella (EN MMS/EP)	Date:	2020-07-28

DO NOT COPY OR REPRODUCE THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF CERN


- Co-authorship of 10 procedures related to electrical quality assurance of LHC and HL-LHC superconducting circuits
- Prototype crab cavity assembly procedure



Acceptance tests of superconducting components of the XFEL accelerator




IFJ PAN in-kind contribution to the XFEL 2010 – 2016






TEST - What does it mean ?



Cavity test main flow diagram


Cryomodule test main flow diagram



TEST

The test program is realized according to the written procedures

Very time consuming and laborious





Unloading of the cryomodule after transport



Cryomodule preparation area



Cryomodule test stand



Cryomodule test stand – module inside



Cryomodule test stand – front view






Main tasks:

- Unload the cryomodule from the truck
- Incoming checks
- Load the cryomodule to the movable support
- Assembling Cryomodule at the test stand
- Connecting Cryomodule beam line to the test stand under clean room conditions
- Leak check of beam line interconnections and mass spectroscopy of the beam line
- Connecting of the waveguides
- Connecting of all electrical cables
- Connect of all cryomodule process pipes to the test stands
- Leak check of cryomodule vessel (ISO-VAC)
- Leak check of cryomodule cryogenic lines
- Assembly and isolating thermal shields
- Pumping down of isolation vacuum





Vertical Cryostat



Radiation protection shielding



Cavity preparation area



Cavity storage area



Cavity incoming check area




Clean room




Main tasks:

- Incoming checks
- Assembling Cavity to the Insert
- Connecting Cavity to the vacuum line (in cleanroom conditions)
- Tuning of Fundamental Mode Rejection Filters of both HOM couplers + Cables connection
- Leak check of the Cavity
- Transport of the Insert to the cryostat + vacuum connection





XFEL Procedures



Number of created procedures:

~50 for Cryomodule (AMTF)
~19 for Cavity (AMTF)

~146 for Cryomodule (CMTB)
~21 for Cavity (HALL 3)

Activation and deactivation of Ion Pump	D00000006689411	09.02.2016
Activation of Titanium Sublimation Pump (TSP)	D00000006689491	09.02.2016
Alignment_of_the_cryomodule	D00000006678751	26.01.2016
Assembly final tightening and connection of GRP adapter	D00000006651881	26.01.2016
Cavities fine tuning and module calibration	D00000006630821	11.12.2015
Closing of the sliding muff	D00000006650681	20.01.2016
Connection of all process pipes	D00000006651941	26.01.2016
Connection of the beamline	D00000006790331	24.03.2016
Connection_of_the_waveguides	D00000006853821	25.04.2016
COOL DOWN_XATB	D00000006563271	08.01.2016
COOL DOWN_XATB_checklist	D00000006552401	09.01.2016
Coupler tuner bellow check at warm	D00000006637781	18.12.2015
Cryomodule Heat Loads measurements	D00000006710641	23.03.2016
Detune all cavities after cold test	D00000006632411	14.12.2015
Disconnection of all process pipes	D00000006652001	21.01.2016
Disconnection of the beamline	D00000006790571	24.03.2016
Disconnection_of_the_waveguides	D00000006853921	25.04.2016
Dismounting of GRP adapter	D00000006652061	26.01.2016
Flat - top measurement	D00000006638681	18.12.2015
Heat Loads Measurements at 2K RF	D00000006637201	18.12.2015
Installation of the 80K thermal shield at End-cap and Feed-cap sides	D00000006678511	26.01.2016
Installation of the 8K thermal shield at End-Cap and Feed-cap sides	D00000006678461	26.01.2016
Integral leak check of the cryomodule	D00000006633341	15.01.2016
Isolating of all process pipes	D00000006652431	20.01.2016
Isolation of the 80K thermal shield using MLI at End-cap and Feed-cap sides	D00000006678631	26.01.2016
Isolation of the 8K thermal shield using MLI at End-cap and Feed-cap sides	D00000006678571	26.01.2016
Leak check of the cryomodule	D00000006711021	15.02.2016
LLRF measurements at AMTF	D00000006637721	05.01.2016
Low power RF measurement at 2K	D00000006630761	11.12.2015
Magnet test at 2K	D00000006632351	21.12.2015
Opening and closing of the cold valve	D00000006710831	15.02.2016
Opening of the sliding muff	D00000006651091	20.01.2016
Post caps installation	D00000006651331	20.01.2016
Pumping down of the cryomodule insulation vacuum	D00000006789801	24.03.2016
Removal of Post caps	D00000006651391	20.01.2016
Removal of the transport-cap at downstream side	D00000006651451	21.01.2016
Removal of the transport-cap at upstream side	D00000006651501	21.01.2016
Unloading of the XFEL cryomodule from the trailer and transfer to the preparation area	D00000006678691	26.01.2016
Vacuum incoming inspection for cryomodule	D00000006632481	15.01.2016
Warm coupler conditioning	D00000006637261	18.12.2015




Concluding



T2K, J-PARC
BELLE 2, KEK

CTA
Pierre Auger



ESS
LUND

E-XFEL
DESY

W7X
IPP GREIFSWALD

SPIRAL 2
GANIL, CAEN

IFJ PAN
KRAKÓW

FAIR
GSI DARMSTADT

LHC, ATLAS
CERN

ITER
CADARACHE

F4E
BARCELONA

Quality Assurance

Quality assurance can be defined as "part of quality management focused on providing confidence that quality requirements will be fulfilled." The confidence provided by quality assurance is twofold—internally to management and externally to customers, government agencies, regulators, certifiers, and third parties.

Quality Control

Quality control can be defined as "part of quality management focused on fulfilling quality requirements." While quality assurance relates to how a process is performed or how a product is made, quality control is more the inspection aspect of quality management.




QC focuses on the results of the work performed, whereas QA is concerned with the adequacy of the underlying processes, methodology, and standards in place to create the output.



This standard describes the fundamental concepts and principles of quality management which are universally applicable to the following:

- organizations seeking sustained success through the implementation of a quality management system;
- customers seeking confidence in an organization's ability to consistently provide products and services conforming to their requirements;
- organizations seeking confidence in their supply chain that product and service requirements will be met;
- organizations and interested parties seeking to improve communication through a common understanding of the vocabulary used in quality management;
- organizations performing conformity assessments against the requirements of ISO 9001;
- providers of training, assessment or advice in quality management;
- developers of related standards.







Action plan - design and optimization

STEP I

Required to perform ~10% tests of the all tested component




RESULT




STEP II

Required to perform ~10% tests of the rest tested component



Optimal result



Optimal design of the action plan for testing object

Improvement and approval of the procedures



Data management - systems

- **quality control**
- **problem analysis**
- automatic report generation (in development)
- electronic logbook

Data Base – Cavity status at AMTF

The screenshot displays a complex data management interface. At the top, there's a navigation pane with options like 'Main', 'Vertical', 'Preparation', 'Cables', 'Reports', and 'AMTF Status'. Below this is a grid of small icons representing different cavities, each with a status indicator. A central table lists tasks with columns for 'Task', 'Status', 'Location', and 'Time'. A large log window on the right shows a detailed list of activities, including 'Arrival of the cryomodule', 'Shock loggers exchange', 'Transport form the truck to the preparation area', and 'Removal of the transport caps', with columns for 'Permission', 'No. Step', 'Location', 'Comments', 'Time', and 'Responsible'.

Data Base – cryomodule tasks XFEL

Screen at hall

This screenshot shows two main panels: 'CAVITIES' and 'MODULES'. The 'CAVITIES' panel is divided into 'Preparation Area' and 'Vertical teststand' sections. The 'Preparation Area' shows a grid of cavity status icons with columns for 'Prep. 1', 'Prep. 2', and 'Prep. 3'. The 'Vertical teststand' section shows details for 'XATC1' and 'XATC2'. The 'MODULES' panel shows a table of module teststands (XATB1, XATB2, XATB3) with columns for 'Module teststand', 'Status', and 'Temperature'. A large digital display in the center shows '10:39' and a temperature of '-4°C'.

The screenshot shows a vertical checklist titled 'Cryomodule tests'. It lists various tasks with status indicators (exclamation marks) and checkboxes. The tasks include: 'M0 "Leszek"', 'M1 "Marek"', 'Loading area', 'Preparation area', 'Incoming inspection', 'Removal of cavity transportation blocking system', 'Pump and purge process for the insulation vacuum', 'Leak check of the insulation vacuum', 'Rough leak check of the insulation vacuum', 'Final leak check of the insulation vacuum', 'Initial conditions', 'List of checked elements', 'Venting of the insulation vacuum', 'Alignment check of cavities', 'Installation of cavities supporting fixture used for transport cryomodule', 'Pump and purge process for the insulation vacuum', 'Leak check of the access hatches', 'Venting of the insulation vacuum', 'Preparation of the module to transportation to the bunker', 'Transportation to the bunker', 'Pump and purge process for the insulation vacuum - VERSION 1', 'Bunker (preparation to cold test)', 'Bunker (cold operations)', and 'Bunker disconnection after the...'. A red box highlights the 'List of checked elements' section.

Cryomodule tasks ESS